PEDESTRIAN MEDALLION PATHS - GENERAL NOTES

GENERAL

1. ALL CONCRETE AND REINFORCEMENT MATERIALS AND PLACEMENT MUST COMPLY WITH SECTION 5.1 OF THE CITY OF WACO STANDARD SPECIFICATIONS FOR CONSTRUCTION.

2. PLEASE REFER TO CITY OF WACO MANUAL OF STANDARD DETAILS G-7 FOR GENERAL CONCRETE AND REINFORCEMENT NOTES.

LOCATION

3. LOCATION INTENDED FOR SELECTED SIDEWALK IN DOWNTOWN DISTRICT WITH C-4 ZONING. SUBMITTALS MUST BE REVIEWED AND APPROVED BY PLANNING.

CONSTRUCTION

4. TOOL ALL EXPOSED EDGES (TYPICAL).

5. PEDESTRIAN MEDALLION PATHS AT CROSSWALKS SHALL BE INSTALLED TO MATCH EXISTING STREET CROSS SLOPE. H.M.A.C. LEVEL-UP SHALL BE PLACED SO AS TO PROVIDE A SMOOTH TRANSITION. CONTRACTOR SHALL VERIFY THAT THE PEDESTRIAN CROSSING AND LEVEL-UP WILL ALLOW POSITIVE STREET DRAINAGE.

6. SAW CUT AND REMOVE EXISTING PAVEMENT AS REQUIRED FOR SMOOTH TRANSITION.

7. SAKRETE® PAVER SET POLYMERIC SAND™ SHALL BE CLEANED FROM TOP OF BRICKS AND WALKWAY.

PAVEMENT AND SIDEWALK LEVEL ALIGNMENT:

8. FOR MAINLINE PAVEMENTS IN LONGITUDINAL DIRECTION, THE GAP BELOW A 10 FT. UNLEVELED STRAIGHT EDGE RESTING ON HIGH SPOTS SHALL NOT EXCEED 1/8 IN.

9. FOR MAINLINE PAVEMENTS IN TRANSVERSE DIRECTION, THE GAP BELOW A 10 FT. UNLEVELED STRAIGHT EDGE RESTING ON HIGH SPOTS SHALL NOT EXCEED 1/4 IN.

10. FOR RAMPS, SIDEWALKS, AND INTERSECTIONS, IN ANY DIRECTION, THE GAP BELOW A 10 FT. UNLEVELED STRAIGHT EDGE RESTING ON HIGH SPOTS SHALL NOT EXCEED 1/4 IN.