

STORMWATER DRAINAGE - GENERAL NOTES

1. REINFORCED CONCRETE PIPE SHALL BE ASTM DESIGNATION C76 CLASS III.
2. PRE-CAST INLETS AND MANHOLES SHALL BE PER TXDOT GUIDE TO THE STANDARD INLET AND MANHOLE PROGRAM STANDARDS. CAST IN PLACE INLETS AND MANHOLES SHALL BE PER COW STANDARDS.
3. SEE PLAN-PROFILE SHEETS FOR INLET SIZE, LOCATION AND ELEVATIONS.
4. WHERE GROUNDWATER IS ENCOUNTERED, ALL LOOSE AND SPONGY MATERIAL WILL BE REMOVED AND 6 IN. MINIMUM 3/4 IN. WASHED ROCK WILL BE INSTALLED FOR BASE.
5. 3/4 IN. WASHED ROCK SHALL MEET THE REQUIREMENTS OF STANDARD SPECIFICATIONS FOR CONSTRUCTION ITEM A.2.a, CRUSHED STONE EMBEDMENT, OF SECTION 4.2 PART 2, EXCEPT THE GRADATION SHALL BE:

3/4 IN. WASHED ROCK	
SIEVE	PERCENTAGE RETAINED
1 1/2 IN.	0%
3/4 IN.	100%

6. THE SIZE AND SPACING OF INLETS MUST COMPLY WITH CURRENT CITY DRAINAGE POLICIES.
7. MANHOLE INLET RING AND COVER SHALL BE IN ACCORDANCE WITH STANDARD DETAIL SD-9.
8. TOP OF INLET SLOPE SHALL CONFORM TO ADJACENT PARKWAY GRADES AND NOT EXCEED 1/2 IN. PER FOOT SLOPE.
9. CONCRETE FOR INVERTS ON ALL MANHOLES AND INLETS SHALL BE PLACED AND SHAPED WITH THE MINIMUM CONCRETE THICKNESS EQUAL TO THE THICKNESS OF THE RCP.

CAST IN PLACE GENERAL NOTES:

10. CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 3000 POUNDS PER SQUARE INCH AT 28 DAYS UNLESS OTHERWISE NOTED. DESIGN MIX FOR 3000 POUND CONCRETE SHALL CONTAIN A MINIMUM OF 5 SACKS OF CEMENT PER CUBIC YARD.
11. REINFORCING STEEL COVER SHALL BE MINIMUM 2 IN. FORMED AND 3 IN. AGAINST EARTH IF UNFORMED FROM OUTSIDE LAYER OF STEEL TO FACE OF CONCRETE.
12. REINFORCED STEEL SHALL BE NEW BILLETED CONFORMING TO ASTM SPECS A615 GRADE 60 OR LATEST REVISIONS.
13. CONSTRUCTION JOINTS WILL BE PERMITTED AS SHOWN ON PLANS.
14. DIMENSIONS RELATING TO REINFORCING STEEL SHALL BE TO OUTSIDE OF BAR NEAREST TO FACE OF CONCRETE.
15. CITY OF WACO INLET SIZES NOTED ON PLAN & PROFILE SHEETS REFER TO DIMENSION "A". DIMENSION "A" MINIMUM IS 10 FEET.
16. PLACE MANHOLE RING & COVER ADJACENT TO OUTLET PIPE SOFFIT AT BACK WALL.
17. BARS SHALL BE SUPPORTED, SPACED AND ACCURATELY SECURED IN PLACE IN ACCORDANCE WITH SPECIFICATIONS FOR PLACING REINFORCEMENT AND FOR PLACING ACCESSORIES MEETING THE REQUIREMENTS OF THE CURRENT ACI MANUAL OF STANDARD PRACTICE FOR DETAILS AND DETAILING REINFORCED CONCRETE STRUCTURES (ACI 315) WITH LATEST REVISIONS.
18. ALL INTERSECTING WALLS, TOPS, FLOORS, SHALL HAVE "L" BARS IN CORNERS LAPPED 40 BAR DIAMETERS.
19. ALL EXPOSED CORNERS SHALL BE TOOLED OR CHAMFERED TO A 1/2 IN. RADIUS.

PRECAST GENERAL NOTES:

20. PRE-CAST INLET SIZES NOTED ON PLAN & PROFILE SHEETS REFER TO DIMENSION "A". DIMENSION "A" MINIMUM IS 9.5 FEET.
21. PRECAST INLETS TO BE BEDDED WITH MIN. 6 IN. OF 3/4 IN. WASHED ROCK.



**ENGINEERING
DIVISION**



REVISIONS			
NO.	COMMENTS	BY	DATE
##	DESCRIPTION	FL	MM/DD/YYYY

DATE
01/31/2022

SD-1