

---

15 December 2023

**SP 3.6-001 (2013)**

**Standard Specifications for Construction  
City of Waco 2013  
Special Provision Section 3.6 Portland Cement Concrete  
Pavement**

The Standard Specifications for Construction City of Waco 2013  
Section 3.6 Portland Cement Concrete Pavement

Part 3: Execution

A. Construction Methods

9. Monolithic Curb

are hereby revised as follows effective for all Developer projects submitted to the City February 1, 2024 and thereafter; for all City projects with bid opening date of February 1, 2024 and thereafter; and for right-of-way permit requests received December 18 and thereafter:


**Part 3: EXECUTION**

**A. CONSTRUCTION METHODS**

**9. Monolithic Curb –**

Concrete for monolithic curb shall be the same as for the pavement and, if carried back from paving mixer, shall be placed within 20 minutes after being mixed. Concrete may be placed from the separate mixer if desired, but in any case must be placed while the pavement concrete is still plastic. After the concrete has been struck off and sufficiently set, the exposed surfaces shall be thoroughly worked with a wooden float. The exposed edges shall be rounded by the use of an edging tool to the radius indicated on the plans. When the concrete in the curb has been sufficiently set, the inside form shall be carefully removed and the surface may be plastered with a mortar consisting of one part of portland cement and two parts fine aggregate as defined in Section 5.1 Concrete and Reinforcement Part 2: Product A. Materials 13. Mortar for Application. The mortar shall be applied with a template or “mule” made to conform to curb dimensions. All exposed surfaces of curb shall be brushed to a smooth and uniform surface.

Sincerely,

  
Thomas M. Dahl, P.E.